

# **TR-115**

## **VDSL2 Functionality Test Plan**

**Issue: 1 Corrigendum 2**  
**Issue Date: February 2011**

**Notice**

The Broadband Forum is a non-profit corporation organized to create guidelines for broadband network system development and deployment. This Broadband Forum Technical Report has been approved by members of the Forum. This Broadband Forum Technical Report is not binding on the Broadband Forum, any of its members, or any developer or service provider. This Broadband Forum Technical Report is subject to change, but only with approval of members of the Forum. This Technical Report is copyrighted by the Broadband Forum, and all rights are reserved. Portions of this Technical Report may be copyrighted by Broadband Forum members.

This Broadband Forum Technical Report is provided AS IS, WITH ALL FAULTS. ANY PERSON HOLDING A COPYRIGHT IN THIS BROADBAND FORUM TECHNICAL REPORT, OR ANY PORTION THEREOF, DISCLAIMS TO THE FULLEST EXTENT PERMITTED BY LAW ANY REPRESENTATION OR WARRANTY, EXPRESS OR IMPLIED, INCLUDING, BUT NOT LIMITED TO, ANY WARRANTY:

- (A) OF ACCURACY, COMPLETENESS, MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE, NON-INFRINGEMENT, OR TITLE;
- (B) THAT THE CONTENTS OF THIS BROADBAND FORUM TECHNICAL REPORT ARE SUITABLE FOR ANY PURPOSE, EVEN IF THAT PURPOSE IS KNOWN TO THE COPYRIGHT HOLDER;
- (C) THAT THE IMPLEMENTATION OF THE CONTENTS OF THE TECHNICAL REPORT WILL NOT INFRINGE ANY THIRD PARTY PATENTS, COPYRIGHTS, TRADEMARKS OR OTHER RIGHTS.

By using this Broadband Forum Technical Report, users acknowledge that implementation may require licenses to patents. The Broadband Forum encourages but does not require its members to identify such patents. For a list of declarations made by Broadband Forum member companies, please see <http://www.broadband-forum.org>. No assurance is given that licenses to patents necessary to implement this Technical Report will be available for license at all or on reasonable and non-discriminatory terms.

ANY PERSON HOLDING A COPYRIGHT IN THIS BROADBAND FORUM TECHNICAL REPORT, OR ANY PORTION THEREOF, DISCLAIMS TO THE FULLEST EXTENT PERMITTED BY LAW (A) ANY LIABILITY (INCLUDING DIRECT, INDIRECT, SPECIAL, OR CONSEQUENTIAL DAMAGES UNDER ANY LEGAL THEORY) ARISING FROM OR RELATED TO THE USE OF OR RELIANCE UPON THIS TECHNICAL REPORT; AND (B) ANY OBLIGATION TO UPDATE OR CORRECT THIS TECHNICAL REPORT.

Broadband Forum Technical Reports may be copied, downloaded, stored on a server or otherwise re-distributed in their entirety only, and may not be modified without the advance written permission of the Broadband Forum.

The text of this notice must be included in all copies of this Broadband Forum Technical Report.

**Issue History**

<b>Issue Number</b>	<b>Issue Date</b>	<b>Issue Editor</b>	<b>Changes</b>
00	February 2011	Michael Hanrahan, Huawei Technologies	Original

Comments or questions about this Broadband Forum Technical Report should be directed to [info@broadband-forum.org](mailto:info@broadband-forum.org).

**Editor:** Michael Hanrahan Huawei Technologies

**Metallic Transmission  
WG Chair** Les Brown Lantiq

**Vice Chairs** Lincoln Lavoie UNH-IOL  
Massimo Sorbara Ikanos

**Chief Editor** Michael Hanrahan Huawei Technologies

**Table of Contents**

**EXECUTIVE SUMMARY ..... 5**

**1 PURPOSE ..... 6**

**2 CORRECTION TO TABLE 18/TR-115..... 7**

**3 CORRECTION TO TABLE 23/TR-115..... 10**

**4 CORRECTION TO TABLE 24/TR-115..... 13**

**5 CORRECTION TO TABLE 32/TR-115..... 16**

**6 CORRECTION TO TABLE 33/TR-115..... 18**

**7 CORRECTION TO TABLE 38/TR-115..... 20**

**8 CORRECTION TO TABLE 45/TR-115..... 21**

## **Executive Summary**

The document contains corrections to TR-115 Issue 1.

## **1 Purpose**

The corrections specified in the following sections apply to *TR-115 Issue 1*.

Note: This corrigendum assumes all previous corrigenda on *TR-115 Issue 1* have been previously applied.

## 2 Correction to Table 18/TR-115

Update **Table 18/TR-115** as follows

**Table 18 – Bit swap Test**

<p><b>Test Configuration</b></p>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) Set up the loop simulator to:</p> <ul style="list-style-type: none"> <li>a. 1350 ft 26AWG</li> <li>or</li> <li>b. 450 m PE 0.4mm</li> </ul> <p>(3) According to the band-profile to be tested, configure the VTU-O with one of the profile line combinations associated to that band-profile (see section 4.2.3). If for the specific band-profile, profile-line combination is defined with DPBO and/or UPBO enabled, these SHALL be applied. The test SHALL be repeated for both the F-1/0 and I-8/2 settings.</p> <p>(4) All single frequency tone amplitudes that are applied are referenced in terms of power levels (dBm) at the injection point on the loop, calibrated with the VTU-R and VTU-O modems replaced with calibrated 100 Ohm <math>\pm 1\%</math> resistors. Measurements performed into a 1kHz resolution bandwidth.</p> <p>Note that with a 1kHz resolution bandwidth the power spectral density value (in dBm/Hz) will be 30dB less than the power level (in dBm), limited by the noise floor of the test equipment used for calibration.</p> <p><u>(5) Set the noise generator to -140 dBm/Hz AWGN noise at both VTU-O and VTU-R.</u></p>
<p><b>Method of Procedure</b></p>	<p>(1) <del>Connect the VTU-O and VTU-R. Wait for the modems to sync. With -140dBm/Hz AWGN noise added at both the VTU-O and VTU-R ends, initialize the link to stable Showtime.</del></p> <p>(2) Wait for 1 minute after <del>completion of</del> initialization.</p> <p>(3) Record the bits allocation tables BITSpsus and BITSpsds.</p> <p>(4) Randomly select an integer value, n, the tone number in the range of one of the bands (DS or US) applicable to the chosen band-</p>

profile. Avoid the use of the pilot tone or any unpopulated tones. Ensure that the tone selected has assigned bits as described in the relevant bits per tone map, also after the injection of the RFI in MOP(5). The frequency of the interfering tone SHALL be set to n x 4.3125 kHz.

- (5) The interfering tone SHALL be applied at the VTU-R side in the downstream bit swap test and at the VTU-O side in the upstream bit swap test. Its power SHALL be -110 dBm or less. Wait 60 seconds. The power of the interfering tone SHALL be -110 dBm or less.
- (6) Record and report the value of n used.
- (7) Record BITSpsus and BITSpsds, and document them as BITSpsus\_Old and BITSpsds\_Old respectively.

- (8) Calculate and record the Transmitted Bits\_US\_Old:

$$\sum_i BITSpsus_i - \left\lceil \frac{NCUSEDus - \frac{NCONEBITus}{2}}{2} \right\rceil - 4$$

and the Transmitted Bits\_DS\_Old:

$$\sum_i BITSpsds_i - \left\lceil \frac{NCUSEDds - \frac{NCONEBITds}{2}}{2} \right\rceil - 4$$

where the  $\lceil x \rceil$  notation represents rounding to the next higher integer, the index 'i' denotes the carrier number, NCUSED represents the number of loaded sub-carriers and NCONEBIT is the number of sub-carriers with 1 bit.

Transmitted Bits\_US\_Old and Transmitted Bits\_DS\_Old refer to the information bits from the PMS-TC. (See Figure 9-1/G.993.2)

Calculate  $\sum_i b_i$  of BITSpsus and BITSpsds, and document the results as Total\_Bits\_US\_Old and Total\_Bits\_DS\_Old respectively.

- (9) Increase the power of the interfering tone to -50 dBm.

(10) Observe any bit-swapping operation without retraining of the modems or change in the net data rate. After 2 minutes verify the payload and CRC errors have stopped. (There MAY be some initial



	<p><del>errors seen when the signal is first inserted on the line.)</del></p> <p><del>(11)</del>(10) <u>      </u> <del>+2</del> minutes after increasing the tone power, record BITSpsus and BITSpsds, and document them as BITSpsus_New and BITSpsds_New respectively.</p> <p><del>(12)</del>(11) <u>      </u> Calculate and record values of <u>Transmitted_Bits_US_New</u> and <u>Transmitted_Bits_DS_New</u> by using the formulas in (8).</p> <p><u>Transmitted_Bits_US_New</u> and <u>Transmitted_Bits_DS_New</u> refer to the information bits from the PMS-TC. (See Figure 9-1/G.993.2)</p> <p><del>Calculate <math>\sum_i b_i</math> of BITSpsus and BITSpsds, and document the results as Total_Bits_US_New and Total_Bits_DS_New respectively.</del></p> <p><del>(13)</del>(12) <u>      </u> Execute a BER test for 2 minutes.</p> <p><del>(14)</del>(13) <u>      </u> Record the CRC and SES counts at the start and the end of the BER test. Actual number of CRCs and SESs is the difference between these two counts.</p> <p><del>(15)</del>(14) <u>      </u> Record the estimated BER</p> <p><del>(16)</del>(15) <u>      </u> Repeat steps 1 to 1<del>4</del>5 for each band applicable to the chosen band-profile.</p>
<p><b>Expected Result</b></p>	<p>(1) No retrain SHALL occur during the test.</p> <p>(2) BITSpsus_New recorded in step MOP(1<del>0</del>4) SHALL differ from BITSpsus_Old in step MOP(7), if tone n is in the bands of upstream direction.</p> <p>(3) BITSpsds_New recorded in step MOP(1<del>0</del>4) SHALL differ from BITSpsds_Old in step MOP(7), if tone n is in the bands of downstream direction.</p> <p>(4) <del>Total Transmitted_Bits_US_Old</del> SHALL equal <del>Total Transmitted_Bits_US_New</del></p> <p>(5) <del>Total Transmitted_Bits_DS_Old</del> SHALL equal <del>Total Transmitted_Bits_DS_New</del></p> <p>(6) SES (as recorded in step MOP(1<del>3</del>4)) SHALL NOT increase</p> <p>(7) The estimated BER SHALL NOT exceed <math>1e^{-7}</math>.</p>

### **3 Correction to Table 23/TR-115**

Update **Table 23/TR-115** as follows

#### **Table 23 – SOS Test In The Downstream**

<p><b>Test Configuration</b></p>	<p>(1) See Section 4.1 for the test configuration</p> <p>(2) The test SHALL be performed with ONE of the following VDSL2 profile line combinations:</p> <ul style="list-style-type: none"> <li>a. BA17a_RA_I_150_150 with 450 m of PE 0.4mm (European VDSL2overPOTS)</li> <li>or</li> <li>b. BB17a_RA_I_150_150 with 450 m of PE 0.4mm (European VDSL2overISDN)</li> </ul> <p>(3) If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p><u>(4) Specific settings:</u> <u>SRA settings from Table 22</u></p>
<p><b>Method of Procedure</b></p>	<p>(1) With -140dBm/Hz AWGN noise added at both the VTU-O and VTU-R ends, initialize the link to stable Showtime. Wait for 1 minute after completion of initialization.</p> <p>(2) Choose the following settings.</p> <ul style="list-style-type: none"> <li>a. DS Minimum SOS Bit Rate (MIN-SOS-BR-ds): 20000kbps.</li> <li>b. DS SOS time Window (SOS-TIME-ds): 64ms</li> <li>c. DS Minimum Percentage of Degraded Tones (SOS-NTONES-ds): 50</li> <li>d. DS Minimum Number of normalized CRC anomalies (SOS-CRC-ds): 1</li> <li>e. DS Maximum Number of SOS (MAX-SOS-ds): 15</li> <li>f. <u>DS SNRM offset for the ROC (SNRMOFFSET-ROC-ds): 6dB</u></li> <li>g. <u>DS INPMIN for ROC (INPMIN-ROC-ds): 8 symbols</u></li> </ul> <p>NOTE: SOS triggering condition specified by parameter SOS-NTONES is superseded with the number of degraded tones <math>\geq 129</math> (Section 13.4.3.2/G.993.2).</p> <p>(3) Disable SOS function.</p> <p>(4) Add the crosstalk noise defined for the band-profile under test in TR-114 to the AWGN noise at VTU-R side only.</p> <p>(5) Force a new initialization.</p> <p>(6) Two minutes through the Showtime record the downstream net data rate as NDR_REINIT_DS (net data rate in the downstream with crosstalk noise achieved if a re-initialization is to occur).</p> <p><u>(7) Deactivate the line.</u></p> <p><del>(7)</del><u>(8)</u> Remove the crosstalk noise.</p> <p><del>(8)</del><u>(9)</u> Enable SOS function.</p> <p><del>(9)</del><u>(10)</u> Force a new initialization.</p>

	<p><del>(10)</del>(11) <u>Wait for 1 minute after initialization</u><del>Allow to train for 60 seconds to achieve showtime.</del></p> <p><del>(11)</del>(12) Add the crosstalk noise defined for the band-profile under test in TR-114 to the AWGN noise at VTU-R side only.</p> <p><del>(12)</del>(13) Record the net data rate 1 second after the crosstalk is switched on as NDR_SOS_BEG_DS (net data rate in the downstream with crosstalk noise at the end of SOS).</p> <p><del>(13)</del>(14) Record the data rate 3 minutes after the crosstalk is switched on as the NDR_SOS_END_DS (net data rate in the downstream with crosstalk noise at the end of SRA).</p>
<p><b>Expected Result</b></p>	<p>(1) No retrain SHALL occur.</p> <p>(2) NDR_SOS_BEG_DS &gt; MIN-SOS-BR-ds          NDR_SOS_END_DS &gt; MIN-SOS-BR-ds          NDR_SOS_END_DS &gt; 0.8*NDR_REINIT_DS</p>

#### **4 Correction to Table 24/TR-115**

Update **Table 24/TR-115** as follows

##### **Table 24 – SOS Test In The Upstream**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration</p> <p>(2) The test SHALL be performed with ONE of the following VDSL2 profile line combinations:</p> <ul style="list-style-type: none"> <li>a. BA17a_RA_I_150_150 with 450 m of PE 0.4mm (European VDSL2overPOTS)</li> </ul> <p>or</p> <ul style="list-style-type: none"> <li>b. BB17a_RA_I_150_150 with 450 m of PE 0.4mm (European VDSL2overISDN)</li> </ul> <p><u>(3)</u> If, for the specific band-profile, profile-line combinations are defined with DPBO and/or UPBO enabled, these SHALL be applied.</p> <p><u>(4) Specific settings:</u> <u>SRA settings from Table 22</u></p>
<b>Method of Procedure</b>	<p>(1) With -140dBm/Hz AWGN noise added at both the VTU-O and VTU-R ends, initialize the link to stable Showtime. Wait for 1 minute after completion of initialization..</p> <p>(2) Choose the following settings.</p> <ul style="list-style-type: none"> <li>a. US Minimum SOS Bit Rate (MIN-SOS-BR-us): 5000kbps.</li> <li>b. US SOS time Window (SOS-TIME-us): 64ms</li> <li>c. US Minimum Percentage of Degraded Tones (SOS-NTONES-us): 50</li> <li>d. US Minimum Number of normalized CRC anomalies (SOS-CRC-us): 1</li> <li>e. US Maximum Number of SOS (MAX-SOS-us): 15</li> <li><u>f. US SNRM offset for the ROC (SNRMOFFSET-ROC-us): 6dB</u></li> <li><u>g. US INPMIN for ROC (INPMIN-ROC-us): 8 symbols</u></li> </ul> <p>NOTE: SOS triggering condition specified by parameter SOS-NTONES is superseded with the number of degraded tones <math>\geq 129</math> (Section13.4.3.2/G.993.2).</p> <p>(3) Disable SOS function.</p> <p>(4) Add the crosstalk noise defined for the band-profile under test in TR-114 to the AWGN noise at VTU-R side only.</p> <p>(5) Force a new initialization.</p> <p>(6) Two minutes through the showtime record the downstream net data rate as NDR_REINIT_US (net data rate in the upstream with crosstalk noise achieved if a re-initialization is to occur).</p> <p><u>(6)(7) Deactivate the line</u></p> <p><u>(7)(8) Remove the crosstalk noise.</u></p>

	<p><del>(8)</del>(9) Enable SOS function.</p> <p><del>(9)</del>(10) Force a new initialization.</p> <p><del>(10)</del>(11) <u>Wait for 1 minute after initialization</u><del>Allow to train for 60 seconds to achieve Showtime.</del></p> <p><del>(11)</del>(12) Add the crosstalk noise defined for the band-profile under test in TR-114 to the AWGN noise at VTU-O side only.</p> <p><del>(12)</del>(13) Record the net data rate 1 second after the crosstalk is switched on as NDR_SOS_BEG_US (net data rate in the upstream with crosstalk noise at the end of SOS).</p> <p><del>(13)</del>(14) Record the data rate 3 minutes after the crosstalk is switched on as the NDR_SOS_END_US (net data rate in the upstream with crosstalk noise at the end of SRA).</p>
<p><b>Expected Result</b></p>	<p>(1) No retrain SHALL occur.</p> <p>(2) NDR_SOS_BEG_US &gt; MIN-SOS-BR-us                  NDR_SOS_END_US &gt; MIN-SOS-BR-us                  NDR_SOS_END_US &gt; 0.8*NDR_REINIT_US</p>

## 5 Correction to Table 32/TR-115

Update Table 32/TR-115 as follows

**Table 32 – Downstream Power Back-Off Test**

<p><b>Test Configuration</b></p>	<p>(1) The VTU modems SHALL be connected as shown in Section 4.1</p> <p>(2) The test setup SHALL support the PSD mask and aggregate transmit power (ATP) measurements over the entire downstream bands and SHALL provide enough dynamic range to allow the measurements be done over both the passband and stopband frequencies into a resolution bandwidth less than or equal to 10 kHz.</p> <p>(3) Configure the VTU-O with the general line setting “F-1/0” defined in Section 4.2.2.2.</p> <p>(4) According to the band-profile to be tested, configure the VTU-O with one of the profile line combinations associated with that band-profile (see 4.2.3 ).</p> <p>If, for the specific band-profile, profile-line combinations are defined with UPBO enabled, apply the related UPBO configuration parameters. <del>Otherwise define one set of UPBO parameters (a, b) for each upstream band</del> <u>If, for the specific band-profile, profile-line combinations are defined with DPBO enabled, apply the related DPBO configuration parameters. Otherwise define one set of DPBO parameters (DPBOEPSD, DPBOESCMA, -B, -C, DPBOMUS, DPBOFMIN, DPBOFMAX).</u></p> <p>(5) Line simulator SHALL be set up for the straight homogeneous loop specified for the regional annex Section 4.4. Its length SHALL be set to the length at which the loop is the equivalent of 20dB @ 1MHz. Alternatively, a flat attenuator MAY be used to perform the measurements, provided its value matches the attenuation of the equivalent loop at 1MHz.</p>
----------------------------------	---



<b>Method of Procedure</b>	<p>(1) Set spectrum analyzer for the requested frequency range, resolution bandwidth and input attenuation range to prevent it from being overridden.</p> <p>(2) Define DPBOESEL in the range of 10 dB to 60 dB, in 10 dB steps.</p> <p>(3) Force initialization and wait for modems to synchronize.</p> <p>(4) Wait 1 minute following synchronization.</p> <p>(5) Disconnect the line. The VDSL2 link SHOULD stay in L0 <del>stay</del> long enough for the PSD to be measured. If it does not see the Note in Table 28.</p> <p>(6) PSD SHALL be measured, while ATP could be measured or calculated from the PSD. in one of the following ways:</p> <ul style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe</li> <li>b. over a wideband 50:100 BALUN transformer (assumes 50ohm analyser)</li> </ul> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an affect of <math>\leq 0.5\text{dB}</math> on the measurement</p> <p>(7) Take a note of the measured PSD data.</p> <p>(8) Take a note of the measured or calculated ATP.</p> <p>(9) Repeat the test steps 3 through 8 for all DPBOESEL values (20dB, 30dB, 40dB, 50dB and 60dB) defined in step 2</p>
<b>Expected Result</b>	<p>(1) Measured PSD mask SHALL comply with the requirements from Section 7.3.1.2.13/G.997.1 and SHALL not exceed the resultant mask (RESULTMASK).</p>

## 6 Correction to Table 33/TR-115

Update **Table 33/TR-115** as follows

**Table 33 – Upstream Power Back-Off Test**

<p><b>Test Configuration</b></p>	<p>(1) The VTU modems SHALL be connected as shown in Section 4.1</p> <p>(2) The test setup SHALL support the PSD mask and aggregate transmit power (ATP) measurements over the entire upstream bands and SHALL provide enough dynamic range to allow the measurements be done over both the passband and stopband frequencies into a resolution bandwidth less than or equal to 10 kHz.</p> <p>(3) Configure the VTU-O with the general line setting “F-1/0” defined in Section 4.2.2.2.</p> <p>(4) According to the band-profile to be tested, configure the VTU-O with one of the profile line combinations associated with that band-profile (see 4.2.3 ).</p> <p>If, for the specific band-profile, profile-line combinations are defined with DPBO enabled, apply the related DPBO configuration parameters. <del>Otherwise define one set of DPBO parameters</del> <u>If, for the specific band-profile, profile-line combinations are defined with UPBO enabled, apply the related UPBO configuration parameters. Otherwise define one set of UPBO parameters (a, b) for each upstream band.</u></p> <p>(5) Line simulator SHALL be set up for the straight homogeneous loop specified for the regional annex, <u>as referenced in</u> Section 4.4 Its length SHALL be set to the length at which the loop is the equivalent of:</p> <ul style="list-style-type: none"> <li>a. 0dB @ 1MHz;</li> <li>b. 10dB @ 1MHz;</li> <li>c. 20dB @ 1MHz</li> </ul> <p>Alternatively, a flat attenuator MAY be used to perform the measurements, provided its value matches the attenuation of the equivalent loop at 1MHz</p>
----------------------------------	--

<b>Method of Procedure</b>	<p>(1) Set spectrum analyzer for the requested frequency range, resolution bandwidth and input attenuation range to prevent it from being overridden.</p> <p>(2) Force initialization and wait for modems to synchronize.</p> <p>(3) Wait 1 minute following synchronization.</p> <p>(4) Disconnect the line. The VDSL2 link SHOULD stay in L0 <del>stay</del> long enough for the PSD to be measured. If it does not see the Note in Table 28.</p> <p>(5) PSD SHALL be measured, while ATP could be measured or calculated from the PSD, in one of the following ways:</p> <ul style="list-style-type: none"> <li>a. over a resistive load of 100 ohms (the same value as the VTU termination impedance) and a high-impedance differential probe</li> <li>b. over a wideband 50:100 BALUN transformer (assumes 50ohm analyser)</li> </ul> <p>If the characteristic of the balun or resistor is not calibrated out, it SHALL have an affect of <math>\leq 0.5\text{dB}</math> on the measurement</p> <p>(6) Take a note of the measured PSD data.</p> <p>(7) Take a note of the measured or calculated ATP.</p> <p>(8) Take a note of the estimated electrical length <math>kl_0</math> (UPBOKLE).</p> <p>(9) Repeat the test steps MOP(2) through MOP(8) for all three loop lengths (between NULL loop and the defined maximum loop) according to the test configuration TC(5).</p> <p>(10) Maintaining the test loop equivalent to 20 dB @ 1MHz.</p> <p><u>(11)</u> Force the VTU-R to use the electrical length <math>kl_0</math> configured by the CO-MIB (UPBOKL) to compute the UPBO. Set the <math>kl_0</math> value to 15dB and repeat steps 2 through 7.</p>
<b>Expected Result</b>	<p><u>(1)</u> Measured PSD mask SHALL comply with the requirements from Section 7.2.1.3.2/G.993.2 [2] and SHALL not exceed the reference UPBO mask (UPBOMASK).</p>

## 7 Correction to Table 38/TR-115

Update Table 38/TR-115 as follows

**Table 38 – MINSNRM Control Test**

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration.</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT in one of the profile line combinations associated to that band-profile in the rate adaptive mode (see Section 4.2.3).</p> <p>(3) <del>Additional-SNRM</del> test conditions:</p> <p style="padding-left: 20px;"><del>a. MINSNRM = 1dB, 2dB and 35dB and TARSNRM=9dB</del></p> <p style="padding-left: 20px;"><del>b. MINSNRM=8dB and TARSNRM=12dB</del></p> <p><u>(4) Connect VTU-R and VTU-O through the 300m PE04 or 1kft 26AWG</u></p> <p><u>(5) Additional test conditions: OPTIONAL OLR (SRA, SOS) SHALL NOT be used.</u></p>
<b>Method of Procedure</b>	<p><del>(1)Connect VTU-R and VTU-O through the shortest loop length defined for the chosen profile line combination in the regional annex of TR-114.</del></p> <p><del>(2)(1)</del> Inject <del>-140-120</del>dBm/Hz AWGN noise added at both the VTU-R and VTU-C ends. This power level is considered the 0dB noise power.</p> <p><del>(3)(2)</del> Let the modems train. Wait for 1 minute after initialization.</p> <p><del>(4)Record the reported SNR margin. SNRMds and SNRMus</del></p> <p><del>(5)(3)</del> Increase the noise power level by <del>16</del>dB. <del>Wait for 1 minute.</del></p> <p><del>(6)Record the reported SNR margin.</del></p> <p><del>(7)(4)</del> <u>Repeat step 5 until the reported SNR margin becomes lower than MINSNRM Wait not more than 90 seconds for modem to retrain.</u></p> <p><del>(8)(5)</del> <u>Repeat the test for each MINSNRM all SNRM test conditions.</u></p>
<b>Expected Result</b>	<p><del>(1) For each test all SNRM test conditions Modems-modems SHALL retrain, if the reported SNR margin is lower than MINSNRM.</del></p>

## 8 Correction to Table 45/TR-115

Update Table 45/TR-115 as follows

Table 45 - SES Counter Reporting Test

<b>Test Configuration</b>	<p>(1) See Section 4.1 for the test configuration</p> <p>(2) As per VDSL2 band-profile to be tested, configure the SUT according to Section 4.2 in <del>FX_I_010_001_RA_F_150_150 and RA_I_150_150</del> specific line-setting defined in Table 11</p> <p>(3) Additional test conditions: <u>OPTIONAL OLR (SRA, SOS) SHALL NOT be used.</u></p> <p style="text-align: center;"><del>a.optional-OLR (SRA, SOS) SHALL NOT be used.</del></p>
<b>Method of Procedure</b>	<p>(1) Connect VTU-R and VTU-O <del>with 0 length loop and no noise injected through 1350 feet 26AWG or 450 m PE04.</del></p> <p><u>(2) Set the noise generator to -120dBm/Hz AWGN at the VTU-R and at the VTU-O side of the loop.</u></p> <p><del>(2)</del><u>(3) Force an initialization and wait for modem to sync.</u> Wait 1 minute following synchronization.</p> <p><del>(3)</del><u>(4) Note down the initial value of the SES-L, SES-LFE, UAS-L and UAS-LFE performance monitoring counters at the VTU-O and the initial value of the SES-L and UAS-L counters at the VTU-R.</u></p> <p><del>(4)</del><u>(5) Force one 330ms "micro-interruption" every 1s for 2 seconds (a total of 2 micro-interruptions) Inject the noise impulse, -110dBm/Hz AWGN, with duration of 590 ± 10 milliseconds at the VTU-R side of the loop.</u></p> <p><del>(5)</del><u>(6) Repeat previous eventMOP(5) 14 times (for a total of 15 impulse events14 x 2 micro-interruption) with 10s between each event.</u></p> <p><del>(6)</del><u>(7) Force performance monitoring counters update and wait 30 seconds for the counters to be read out.</u></p> <p><del>(7)</del><u>(8) Note down the value of the counter SES-L and UAS-L at the VTU-R. Note down the value of the counters SES-L and SES-LFE, and UAS-L and UAS-LFE at the VTU-O.</u></p> <p><del>(8)</del><u>(9) Calculate the increase of these counters between step 86 and step 43.</u></p> <p><u>(10) Repeat steps 5 to 9, but inject the noise impulse at the VTU-O side of the loop.</u></p>

<b>Expected Result</b>	<ul style="list-style-type: none"><li>(1) No lost of synchronization SHALL occur during the test.</li><li>(2) No increase of UAS-L and UAS-LFE at the VTU-O SHALL be reported during the test time.</li><li>(3) If available, no increase of UAS-L at the VTU-R SHALL be reported.</li><li>(4) The increase of SES-L counter at the VTU-R SHALL be equal to the increase of SES-LFE counter at the VTU-O.</li><li>(5) The increase of SES-L counter at the VTU-R, as well as the increase of both SES-LFE and SES-L counters at the VTU-O, SHALL be at least equal to <del>30-15</del> and <del>less than 45</del> <math>\leq 30</math>.</li></ul>
------------------------	--

End of Broadband Forum Technical Report TR-115